BRUHATH BANGALORE MAHANAGARA PALIKE, DASARAHALLI ZONE
Office of the Executive Engineer
SCHEDULE-B

NAME OF WORK: Improvements to drains at 7th cross L/s Bhuvaneshwari nagara in Ward No 14,

Sl. No	Description of work	Unit	Qty	Sanctioned Approved Rates	
				In Figures (Rs.)	In Words (Rs.)
1	2	3	4	5	6
1	Excavation for road, drains and similar works - KSRRB 300-1. Earthwork excavation by manual means in Ordinary soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods Complete as per specification and direction of Engineer-in-charge of the work.	Cum	167.52	75.60	Rupees Seventy Five and Sixty Paise Only
2	Removing B.S.Slab of drain and stacking etc., Complete as per specification and direction of Engineer-in-charge of the work.	Sqm	72.00	58.32	Rupees Fifty Eight and Thirty Two Paise Only
3	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @180 kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing Complete as per specification and direction of Engineer-in-charge of the work.	Cum	51.66	4847.04	Rupees Four Thousand Eight Hundred Forty Seven and Four Paise Only
4	Providing and laying in position plain cement concrete of mix M1:2:4 with cement @240 kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing Complete as per specification and direction of Engineer-in-charge of the work.	Cum	60.82	5228.98	Rupees Five Thousand Two Hundred Twenty Eight and Ninety Eight Paise Only
5	Refixing stone slabs of drains and pointing in CM 1:3 etc., Complete as per specification and direction of Engineer-in-charge of the work.	Sqm	108.00	75.60	Rupees Seventy Five and Sixty Paise Only
6	Providing Granite slabs selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc., Complete as per specification and direction of Engineer-in-charge of the work.	Sqm	72.00	639.36	Rupees Six Hundred Thirty Nine and Thirty Six Paise Only

Signature of the Contractor

EXECUTIVE ENGINEER-2
KRIDL, BBMP DEMOLITION
BANGALORE - 560 010

Executive Engineer

7	Providing and constructing precast concrete solid blocks with compressive strength not les than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20 cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing Complete as per specification and direction of Engineer-in-charge of the work.	Sqm	160.00	993.60	Rupees Nine Hundred Ninety Three and Sixty Paise Only
8	Providing T.M.T steel reinforcement for R.C.C. work including straightening, cutting, bending, hooking, placing in position, lapping and/or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery Complete as per specification and direction of Engineer-in-charge of the work.	q	34.10	7835.18	Rupees Seven Thousand Eight Hundred Thirty Five and Eighteen Paise Only
9	Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour Complete as per specification and direction of Engineer-in-charge of the work.	Sqm	438.40	292.68	Rupees Two Hundred Ninety Two and Sixty Eight Paise Only
10	Supplying and fixing precast rainforced concee slab 10cm thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface stc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials. Complete as per specification and direction of Engineer-in-charge of the work.	Sqm	303.30	1600.00	Rupees One Thousand Six Hundred Only
11	Providing and fixing Pre cast solid concrete kerb stones of size 450x200x400mm made out of CC 1:2:4 and finished with CM 1:3 plastering and finishing cutting etc., Complete as per specification and direction of Engineer-in-charge of the work.	No	290.00	357.48	Rupees Three Hundred Fifty Seven and Forty Eight Paise Only
12	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 ..... Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading Complete as per specification and direction of Engineer-in-charge of the work.	Cum	167.52	78.24	Rupees Seventy Eight and Twenty Four Paise Only

Signature of the Contractor

EXECUTIVE ENGINEER-2
KRIDL, BBMP DIVISION
BANGALORE - 560 0..

Executive Engineer,
Dasarahalli Division,

ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆ, ದಾಸರಹಳ್ಳಿ ವಲಯ

ಎಂ.ಇ.ಐ.ಬಡಾವಣೆ, ಬಾಗಲಗುಂಟೆ, ಹೆಸರಘಟ್ಟ ಮುಖ್ಯರಸ್ತೆ, ಬೆಂಗಳೂರು -560073

ಸಂಖ್ಯೆಃಕಾಪಾಅ/ದಾ.ವಿ/ಪಿಆರ್/3047/14-15

ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರವರ ಕಛೇರಿ,
ದಾಸರಹಳ್ಳಿ ವಿಭಾಗ,
ದಿನಾಂಕ: 7/2/2015

ರವರಿಗೆ,

Technical Manger (west),
Karnataka Rural Infrastructure Development Limited,
Project Implementation unit,
No.280, 59th Cross, 17th 'C' Main Road,
3rd 'Y' Block, Rajajinagar.
Bangalore-560 010.

ಮಾನ್ಯರೆ,

ವಿಷಯಃ- ಬೃಹತ್ ಬೆಂಗಳೂರು ಮಹಾನಗರ ಪಾಲಿಕೆಯ ದಾಸರಹಳ್ಳಿ ವಲಯದ ವ್ಯಾಪ್ತಿಯಲ್ಲಿ ತುರ್ತು ಕಾಮಗಾರಿಯನ್ನು ಮೆ//ಕೆ.ಆರ್.ಐ.ಡಿ.ಎಲ್, ವತಿಯಿಂದ ನಿರ್ವಹಿಸುವ ಬಗ್ಗೆ.

ಉಲ್ಲೇಖಃ- "ತೆರಿಗೆ ಮತ್ತು ಆರ್ಥಿಕ ಸ್ಥಾಯಿ ಸಮಿತಿ" ಸಭೆಯ ನಡವಳಿಗಳು ದಿ:05.01.2015ರ ವಿಷಯದ ಸಂಖ್ಯೆ:ತೆಆಸ್ಥಾಸ/93/14-15,

-:-

ಮೇಲ್ಕಂಡ ವಿಷಯಕ್ಕೆ ಸಂಬಂಧಿಸಿದಂತೆ, ದಾಸರಹಳ್ಳಿ ವಿಭಾಗದ ವ್ಯಾಪ್ತಿಯಲ್ಲಿ ಬರುವ ವಾರ್ಡ್ ನಂ.14ರಲ್ಲಿ 2014-15ನೇ ಸಾಲಿನ ಲೆಕ್ಕಶೀರ್ಷಿಕೆ ಪಿ-1771 ಅನುದಾನಡಿಯಲ್ಲಿ ಅಂದಾಜು ಮೊತ್ತ ರೂ.20.00ಲಕ್ಷಗಳಿಗೆ ಈ ಕೆಳಕಂಡ ಕಾಮಗಾರಿಯು ಅನುಮೋದನೆಗೊಂಡಿದ್ದು, ಸದರಿ ಕಾಮಗಾರಿಯನ್ನು ತುರ್ತಾಗಿ ನಿರ್ವಹಿಸಲು, ಉಲ್ಲೇಖ ಪತ್ರದನ್ವಯ ಕರಾರು ಪತ್ರ ಮಾಡಿಕೊಳ್ಳಲು ಈ ಮೂಲಕ ಸೂಚಿಸಲಾಗಿದೆ. ವಿವರಗಳು ಈ ಕೆಳಕಂಡಂತಿರುತ್ತವೆ.

Sl. No	Name of work	Job code	P Code	Est.Cost (Rs in Lakhs)
1.	Improvements to drains at 7th cross L/s Bhuvaneshwari nagara in Ward No 14,	014-15-000032	1771	20.00

ತಮ್ಮ ವಿಶ್ವಾಸಿ
7/2/15
ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು,
ದಾಸರಹಳ್ಳಿ ವಿಭಾಗ,
ಬೆಂಗಳೂರು.

ಕಛೇರಿ ಪ್ರತಿ.